

e.CAB ELEVATOR
4639 LOWN ST N
ST PETERSBURG, FL 33714-2947
US
7275258987
cindi@ecabelevator.com
www.ecabelevator.com

Estimate



ADDRESS

Diplomat #212 Townshores
5980 Shore Blvd S
Gulfport, FL 33707
United States

SHIP TO

Diplomat #212 Townshores
5980 Shore Blvd S
Gulfport, FL 33707
United States

ESTIMATE

8489

DATE

04/29/2025

SALES REP

JT

P.O.

EC8489

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
Sales-Contract	We propose to furnish and install the following for One (1) 2,500 lbs. passenger elevator. Remove existing interiors as required and prepare for the installation of the new interior components. WALLS: (7) new UTL raised plastic laminate panels to be: Wilsonart 7054-60 -Wild Cherry. (Panel configuration - rear wall to have 3 panels and each side wall to have 2 panels) REVEALS, CORNERS, FRIEZE & BASE: New T304 #4 stainless steel with vent slots HANDRAILS: New 1/4" X 2" flat T304 #4 stainless steel handrails with returned ends on Rear wall only. CEILING: New (LT021) lift & lock T304 #4 stainless steel pan ceiling with 6 LED downlight system. Patent No: US 11,584,620 B1 *** Note: Ceiling to be mounted within 4" of car canopy. FRONT RETURN, TRANSOM & JAMBS: To remain the same. FLOORING: New Stanton REJUVENATION Vinyl Flooring. Note: This pricing does not include sub-flooring, if required CAB DOOR: To Remain the same. BRAILLE & TACTILE MARKINGS: To Remain the same.	1	9,867.00	9,867.00

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
Sales-Contract	We propose to furnish and install the following for One (1) 2,500 lbs. passenger elevator. - PLEASE NOTE: This is the Left Elevator cab used for Freight. Remove existing interiors as required and prepare for the installation of the new interior components. WALLS: (7) new UTL raised plastic laminate panels to be: Wilsonart 7054-60 -Wild Cherry. (Panel configuration - rear wall to have 3 panels and each side wall to have 2 panels) REVEALS, CORNERS, FRIEZE & BASE: New T304 #4 stainless steel with vent slots HANDRAILS: New 1/4" X 2" flat T304 #4 stainless steel handrails with returned ends on Rear wall only. CEILING: New (LT021) lift & lock T304 #4 stainless steel pan ceiling with 6 LED downlight system. Patent No: US 11,584,620 B1 *** Note: Ceiling to be mounted within 4" of car canopy. FRONT RETURN, TRANSOM & JAMBS: To remain the same. FLOORING: New Stanton REJUVENATION Vinyl Flooring. Note: This pricing does not include sub-flooring, if required CAB DOOR: To Remain the same. BRAILLE & TACTILE MARKINGS: To Remain the same. PROTECTIVE PAD HOOKS: Please Install Pad Hooks only in this cab. NOTE: Pad Hooks need to be installed to match customers current protective pad grommet holes. This pricing includes 1 mobilization. Elevators must be made available exclusively / consecutively to e.CAB in order to avoid extended downtime and added cost. e.CAB Elevator will work under Elevator Permits. PLEASE NOTE: Any Cab and Cab Door adjustments to be by customer. Terms: 50% deposit and Balance to be paid at the walkthrough and sign off to work. PLEASE NOTE: ANY and ALL CHANGE ORDERS WILL REQUIRE A 100% DEPOSIT. **Initial  Thank You. Joel Tompkins - 727-224-9651 – Cell	1	10,481.00	10,481.00

ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
----------	-------------	-----	------	--------

Quotation is good for 15 days from the date this quote is emailed.

1. Work to be performed during the hours of 7:30am to 5:00 p.m. Monday through Friday.
2. For the quoted price to be honored, this document must become part of any contract documents. In case of contradiction of contract terms, this document shall serve as the prevailing document.
3. In the event the completion of the job is delayed beyond 10 working days, at no fault of e.CAB, e.CAB reserves the right to collect payment for work completed.
4. Any mechanical or weight adjustments that are necessary as a result of e.CAB's work are the responsibility of the owner.
5. e.CAB does not agree to the holding of retainage in any amount.
6. Unless otherwise specified in the quote, no material will be ordered for this job until the required 50% deposit is received.
7. It is advised that upon completion of the project that the owner have a qualified elevator company perform a full load safety test. The cost of this test will never be the responsibility of e.CAB, LLC.

SUBTOTAL	20,348.00
TAX (0%)	0.00
TOTAL	\$20,348.00

Accepted By

Patricia Lytle
President

Accepted Date

May 1, 2025